

BREWARRINA SHIRE COUNCIL



All communications to be addressed to the General Manager
SHIRE OFFICE
57 Bathurst Street
BREWARRINA NSW 2839
PO Box 125
BREWARRINA NSW 2839
Telephone: (02) 6830 5100
Fax: (02) 6839 2100
Email: breshire@brewarrina.nsw.gov.au

Wednesday, 2nd October 2024

Request for Tender T 2024 – 03

Brewarrina Shire Council would like to invite you to submit a tender to construct concrete shared path in the township of Goodooga, as shown below in two (2) stages. The paths (Stage 1 - Magenta L=1.0km, Stage 2 - Orange 0.9km) will be 2.4 meters wide lined up with solar lights for night safety on Queensland Street / Reservoir Road. Allowance for four ramp crossing to be provided. **Works will be required to be completed by January 31st 2025.**



Tenders are to be submitted by Monday 2:00 PM-28th October 2024.

Please complete and return a signed copy of:

- Works Schedule (A) – Quantities & Rates – Stage 1
- Works Schedule (B) – Quantities & Rates – Stage 2

The proposed works are to be constructed in accordance with the attached plan. The conditions of contract will be AS4906 with the following specifics:

- Maintenance period 12 months
- Retention money
5% of the total contract value; 50% returned on issuing practical completion certificate and the final amount released on issuing final completion certification

Quotations should be clearly marked “**Confidential**” – **Tender - T2024 - 03 Construction of Goodooga Concrete Shared Path** and addressed to:

Mr David Kirby
General Manager

Quotation may be submitted in person to Council office in Brewarrina or via post, fax, email, or tenderlink as per the following details

Mail Brewarrina Shire Council
 P.O Box 125 – BREWARRINA, NSW 2839

Email tender@Brewarrina.nsw.gov.au

If you have any other queries in relation to this matter please contact Council’s Technical Services Admin Officer on 02 6830 5100 or by email tsao@brewarrina.nsw.gov.au. Council reserves the right to select the most advantageous quotation that will satisfy the work requirements.

Yours sincerely

Mr Ajnesh Sharma

Transport Manager | Brewarrina Shire Council

Schedule (A) - Quantities & Rates - Stage 1

Item	Description of Works	Quantity	Unit	Rate	Amount
1	Site establishment and management including permits, insurances and liaison with relevant authorities and parties; Traffic Management in accordance with Traffic Control at worksites Technical Manual Environmental Management in accordance with council policy; Location and potholing of existing services prior to undertaking any works; Set-out of works		Item		
2	Excavate and remove existing 225mm of spoil under the proposed path and stockpile. Prepare the subgrade for gravel.		M2		
3	Import, spread and compact 100mm layer of gravel supplied from the Bukulla pit approximately 60kms from the site. Council will supply gravel material at the Airport Gravel pit.		M2		
4	Form & pour a reinforced concrete shared path 2.4m wide. Refer Sheet GD06 for details. A broom finish perpendicular to the path of travel and a edged finish. Refer drawing for path length.		M2		
5	Construct twenty (12) ramps to match the new-shared path. Refer Sheet GD06 for ramp details.		each		
6	Supply and install 5 No. solar lights to agreed specification		No.		
7	Backfill the new-shared path with topsoil and compact and tidy site.		LS		
SUBTOTAL WORKS SCHEDULE (excluding GST)					
GST(10%)					
PROJECT TOTAL (including GST)					

Schedule (B) - Quantities & Rates - Stage 2

Item	Description of Works	Quantity	Unit	Rate	Amount
1	Site establishment and management including permits, insurances and liaison with relevant authorities and parties; Traffic Management in accordance with Traffic Control at worksites Technical Manual Environmental Management in accordance with council policy; Location and potholing of existing services prior to undertaking any works; Set-out of works		Item		
2	Excavate and remove existing 225mm of spoil under the proposed path and stockpile. Prepare the subgrade for gravel.		M ²		
3	Import, spread and compact 100mm layer of gravel supplied from the Bukulla pit approximately 60kms from the site. Council will supply gravel material at the Airport Gravel pit. (1.5m x 2.7m x 100mm)		M ²		
4	Form & pour a reinforced concrete shared path 2.4m wide. Refer Sheet GD06 for details. A broom finish perpendicular to the path of travel and a edged finish. Refer drawing for path length.		M ²		
5	Construct twenty (8) ramps to match the new-shared path. Refer Sheet GD06 for ramp details..		each		
6	Provide allowance to install eight (8) solar lights to agreed specification, if required		No .		
7	Backfill the new-shared path with topsoil and compact and tidy site.		LS		
SUBTOTAL WORKS SCHEDULE (excluding GST)					
GST (10%)					
PROJECT TOTAL (including GST)					

Company Name			
Address			
Phone			
Mobile Phone			
Email			
Signed on Behalf of Company			
Name		Date	